

073206T4BLD

BUILDING TECHNOLOGY LEVEL 6

CON/OS/BUT/CR/02/6

Execute Site Preliminary Works

November/December 2025

Printed By Technical And Vocational College
Date: 20.11.2025 03:24 PM



Printed By: rth Technical And Vocational College Date:
20.11.2025 03:24 PM

TVET CURRICULUM DEVELOPMENT, ASSESSMENT AND CERTIFICATION COUNCIL (TVET CDACC)

WRITTEN ASSESSMENT

Printed By: And Vocational College Date: 20.11.2025 03:24 PM

Time: 3 HOURS

INSTRUCTIONS TO CANDIDATE

Technical And Vocational College

Date: 20.11.2025 03:24 PM

1. This paper consists of **TWO** sections: **A** and **B**.
2. Answer **ALL** questions in section A and **ANY THREE** (3) questions in section B.
3. Marks fston are indicated in the brackets.
4. Candidates are provided with a separate answer bookl.
5. Do not write on the question paper.

Printed By: Technical And Vocational College
Date: 20.11.2025 03:24 PM

Printed By: Technical And Vocational College

Date: 20.11.2025 03:24 PM

Printed By: Technical And Vocational College Date: 20.11.2025
03:24 PM

This paper consists of THREE (3) printed pages

Printed By: Technical And Vocational College

Date: 20.11.2025 03:24 PM

Candidates should check the question paper to ascertain that all pages are printed as indicated and that no questions are missing.

SECTION A (40 MARKS)

Answer ALL the questions in this section.

1. Proper planning and hazards can prevent accidents and save lives. State any other FOUR precautions when executing preliminary works. (4 Marks)
2. Site clearance is a critical activity in a construction site. Outline FOUR major activities done during this exercise. (4 Marks)
3. Most construction sites require site stripping and site grubbing. Distinguish between the two terms. (4 Marks)
4. A construction signboard is a legal and communicative. List FOUR items that must be displayed on a construction site signboard in Kenya. (4 Marks)
5. Welfare facilities are vital for worker well-being and productivity. Name FOUR welfare items that must be provided for workers on a construction site. (4 Marks)
6. Preliminary services are essential for smooth operation of activities. Highlight any THREE services that must be provided before commencement of a construction project. (3 Marks)
7. A lot of waste is produced during site clearance. Indicate THREE objectives of a pre-construction site waste management plan in site clearance. (3 Marks)
8. Construction sites are often divided into different zones to enhance safety and efficiency. Outline FOUR types of zones commonly found on a site. (4 Marks)
9. During the preparation of a site plan, the contractor was required to determine contour lines. Point out FOUR methods of determining contours after reducing levels. (4 Marks)
10. Before construction work, a survey team was engaged to assess the site. Highlight FOUR importance of carrying out surveying site. (4 Marks)
11. Temporary facilities support smooth site operations. List TWO examples of temporary facilities required on a construction site. (2 Marks)

SECTION B (60 MARKS)*Answer Any THREE Questions in This Section*

12. You have been assigned to see the safe demolition of an old warehouse building in an urban area. Printed By: Technical And Vocational College
Date: 20.11.2025 03:24 PM
- Explain any FIVE survey activities that you should do before demolition. (10 Marks)
 - Discuss FIVE possible demolition methods that you would apply to demolish a building. Printed By: Technical And Vocational College
Date: 20.11.2025 03:24 PM (10 Marks)
13. A contractor has been awarded a project to construct a modern office block. To ensure smooth operations, proper site layout planning is required before work begins. Printed By: Technical And Vocational College
Date: 20.11.2025 03:24 PM
- Describe FIVE components that must be considered when planning a construction site layout. (10 Marks)
 - Explain FIVE purposes of preparing a site layout plan on a construction project. (10 Marks)
14. Site Hoarding is a vital component of site management in construction projects.
- Explain TWO classifications of site hoarding giving two applications for each. Printed Technical And Vocational College
Date: 20.11.2025 03:24 PM (8 Marks)
 - Describe SIX purposes of site hoarding. (12 Marks)
15. Assume you have been hired by a certain construction company as a building technician to undertake levelling practical using a dumpy level along one at common intervals of 20m. The first reading is taken on chainage 80m where the RL was 103.565m. The instrument was shifted after the 3rd and 7th readings. The following readings were taken: 3.150, 3.860, 2.125, 0.760, 2.235, 0.470, 1.935, 3.225 and 3.890m. Book the readings on the level note book and find the RL of all points by Printed By: Technical And Vocational College
Date: 20.11.2025 03:24 PM
- Height of collimation method. Printed By: Technical And Vocational College
Date: 20.11.2025 03:24 PM (10 Marks)
 - Rise and fall method. (10 Marks)